

Tender Inviting Authority:CDM &PHO, Kalahandi, Bhawanipatna					
Name of Work: Constuction of Subcentre Building (HWC) at Palna					
Bid Identification No.:01/2021-22 of CDM & PHO Kalahandi					
Bidder Name					
SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
1	Earth work in excavation of foundation in hard soil with all leads and lifts including dressing the sides and levelling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour and T&P,royalty etc. complete and as directed by the Engineer-in-charge.	cum	98.38	186.40	18338.03
2	Filling in foundation & plinth with sand in 22.5cm(9") thick layers including watering and ramming with all cost conveyance royalty, taxes of the materials and labour with T&P required for the work etc. complete or as directed by the Engineer-in-charge.	cum	115.75	319.80	37016.85
3	Plain Cement concrete (1:3:6) with 4cm size C.B, h.g metal of approved quality and from approved quarry including hoisting,lowering, and laying in layers to 10cm(4") thick to required level, ramming,watering including all cost & conveyance of all materials and labour with T&P required for the work with all taxes and royalties complete in all respects and as directed by the EIC.	cum	34.47	4125.70	142212.88
4	Fly ash brick masonry in cement mortar(1:6) after immersing bricks for six hours in water before use in super structure using clamp burnt bricks of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm2 including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge.	cum	22.80	4072.10	92843.88
5	Reinforced cement concrete (1:1.5:3) in foundation , column, beam, slab using 12mm size h.g, C.B. broken hard granite chips of approved quality and from approved quarry including hoisting, lowering and laying in layers not exceeeding 15cm thick to the required level ,compacting,watering and curing etc. including all cost of material, labour, with T&P and taxes & royalty of materials etc. required for work and as per direction of EIC.				
	(A) Column Base	cum	8.85	4520.33	40004.92
	(B) Columns and beams	cum	12.26	11665.34	143017.07
	(C) Plinth bend	cum	6.83	4874.50	33292.84
	(D) Lintel	cum	3.15	8049.00	25354.35
	(E) Chajja	sqm	4.18	755.85	3159.45
	(F) Shelves	sqm	12.05	711.37	8572.01
	(G) Roof slab	cum	15.03	8658.44	130136.35
	(H) Staircase	cum	1.37	9705.63	13296.71
6	Supplying fitting, with Straightening, cutting, bending, cranking, hooking, welding or jointing (if required) the HYS steel and binding wires and binding, tying the grills, hoisting, lowering and placing in proper position as required for R.C.C. works and for providing cost, conveyance and taxes of M.S. rods or Tor steel including binding wires of 18 to 20 gauge and labour with all T&P required for the work etc. completefor ground floor or as directed by the Engineer-in-charge.	Qntl	57.58	8109.58	466949.62
7	Cement concrete (1:2:4) in foundation , column, beam, slab using 12mm size h.g, C.B. broken hard granite chips of approved quality and from approved quarry including hoisting, lowering and laying in layers not exceeeding 15cm thick to the required level compacting,watering and curing etc. including all cost of material, labour, with T&P and taxes & royalty of materials etc. required for work and as per direction of EIC.	cum	6.26	5452.80	34134.53

SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
8	Fly ash brick masonry in cement mortar(1:6) after immersing bricks for six hours in water before use in super structure using clamp burnt bricks of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm2 including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge.	cum	46.31	4110.42	190353.55
9	Fixing of Vitrified tiles in floors or treads on 25mm thick bed of cement mortar (1:1) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge.	sqm	101.89	896.68	91362.73
10	Fixing Ceramic tiles in dados skirting on 12mm thick CP (1:3) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge.	sqm	98.40	1040.30	102365.52
11	Supplying fitting fixing of granite tilesabove 0.40sqm (20mm thick) in floors or treads on 25mm thick bed of cement mortar (1:4) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge.	sqm	6.47	1505.78	9742.40
12	16mm thick cement plaster (1:6) over Brick / stone massonary finished smooth including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge	sqm	291.36	192.09	55967.34
13	12mm thick cement plaster (1:6) over Brick / stone massonary finished smooth including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge	sqm	206.25	127.05	26204.06
14	20mm thick cement plaster (1:6) over Brick / stone massonary finished smooth including punning etc including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge	sqm	27.31	201.35	5498.87
15	Supplying iron shutter M.S. panalled door single leaf with M.S. frame and M.S. panalled window double leaf with M.S. frame and grill etc. with all cost, carriage, taxes etc complete as directed by the EIC.	Kg	1773.66	72.20	128058.25
16	White washing 3 coats with shell lime including cost of Lime etc conveyance, royalties and taxes of all materials and labour with T&P require for the work etc complete in all respect in all follrs or as directed by the EIC	sqm	597.68	16.67	9963.33
17	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete	sqm	323.06	71.75	23179.56
18	Wall painting 2 coats with Plastic paint of approved shade on new work to give an even shade exclding cost of paint.	sqm	323.06	76.79	24807.78

SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
19	Wall painting 2 coats with Weather coat of approved shade on new work to give an even shade including cost of paint etc conveyance, royalties and taxes of all materials and labour with T&P require for the work etc complete in all respect in all follrs or as directed by the EIC	sqm	230.65	71.12	16403.83
20	Painting 2 (Two) coats with any approved enamel paint over a coat of priming to new wood work and iron work including cost of the primer and paint sand papering polishing the surface with cost conveyance and taxes of all materials and labour with T&P required for the work etc. complete in all respect or as directed by the EIC.	sqm	82.42	189.79	15642.49
21	Providing, fitting and fixing up window (sliding type) made up aluminum section 151 - 154, 155-154, as windows frame section No. 151-155, 151-153 and 151-167 as shouter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour t&P etc complete as per direction of EIC.	sqm	3.07	3657.47	11228.43
22	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect.	RM	7.32	3497.00	25598.04
23	Labour for fixing big six or trafford GCI Sheet in roof including fixing of ridges wind tiles etc but excluding cost of fitting including drilling holes in wind ties.	sqm	13.27	443.40	5883.92
24	Labour for collecting moorum conveying & spreading and consolidation with HRR including watering , cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. completer as directed by the Engineer-in-charge	cum	21.23	617.54	13110.37
Total amount				Rs	1943699.95
Total 24 (twenty four) items only					
My Quoted Rate is _____%(both figure and wards)					
Excess over/Less than/equal to the above Tender cost					
-sd-					
Chief Distirict Medical And Public Health Officer Kalahandi					