

Tender Inviting Authority:CDM &PHO, Kalahandi, Bhawanipatna					
Name of Work: Constuction of Labour room At Deypur PHC(N)					
Bid Identification No.:01/2021-22 of CDM & PHO Kalahandi					
Bidder Name					
SCHEDULE OF WORKS					
SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
1.00	Earth work in excavation of foundation in hard soil including dressing and leveling the bed and depositing the soil within 50 m initial lead and 1.5 m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3 m in depth and as per direction of the Engineer-in-charge.	Cum	123.12	184.60	22727.95
2.00	Filling foundation and plinth with sand well watered and rammed including all cost,conveyance,royalties,labour etc.complete.	Cum	157.35	292.70	46056.35
3.00	Cement concrete (1:3:6) using 4cm size h.g.metal including all cost, conveyance, royalties etc.complete.	Cum	46.23	4151.65	191930.78
4.00	Fly ash brick masonry in cement mortar(1:6) for foundation and plinth after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge	Cum	33.70	4041.62	136202.59
5.00	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying.				
6.00	Column base	Cum	12.88	4414.06	56853.09
7.00	Grade beam	Cum	6.11	4767.00	29126.37
8.00	Coloumn and beam	Cum	9.67	10063.60	97315.01
9.00	Lintel	Cum	3.46	7927.58	27429.43
10.00	Chajja	Sqm	7.34	746.65	5480.41
11.00	Roof Slab	Cum	14.63	8531.40	124814.38
12.00	Staircase	Cum	2.04	9565.42	19513.46
13.00	Plain Cement concrete (1:2:4) using 12mm size c.b.h.g.chips including cost,conveyance and royalty etc complete.	Cum	4.08	5428.49	22148.24
14.00	Supplying,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification including cost,conveyance and taxes of all materials.	Qtl	53.93260	7583.80	409014.05
15.00	Fly ash brick masonry in cement mortar(1:6) for superstructure after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge	Cum	54.21	4079.95	221174.09
16.00	16 mm thick cement plaster in c.m(1:6) over brick works including cost, conveyance, royalties, labour, T&P etc.complete.	Sqm	124.36	188.50	23441.86
17.00	12 mm thick Cement plaster in c.m.(1:6) over stone masonry including cost, conveyance, royalties, labour, T&P etc.complete.	Sqm	198.09	124.36	24634.47
18.00	20mm thick cement plaster (1:6) over Brick / stone massonary inished smooth including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge	Sqm	44.6355	197.10	8797.66
19.00	Supplying iron shutter M.S. panalled door single leaf with M.S. frame and M.S. panalled window double leaf with M.S. frame and grill etc. with all cost, carriage, taxes etc complete as directed by the EIC.	kg	615.37	70.00	43075.90
20.00	Fitting, fixing iron shutter M.S. panalled door with M.S. frame and M.S. panalled window with M.S. frame and grill in position etc including fixing in cement concrete CC (1:3:6) with 12mm to 20mm hard stone chips or in cement mortar (1:3) including all cost of materials and as per the direction of EIC.	Sqm	20.86	392.56	8188.80
21.00	Fixing of Vitrified tile in floors of size 600mmX600mm on 25mm thick in c.m.(1:1) joints with neat cement slurry mixed with pigment to match the shades of the times including rubbing & polishing etc.complete.	Sqm	112.61	887.63	99956.01

SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
22.00	Fixing of ceramic tiles in dadoes including skirting dadoes with 12mm thick c.p. in c.m.(1:3) jointed including cost, carriage, labour etc.complete.	Sqm	203.30	910.53	185110.75
23.00	White washing 3 coats with shell lime over plastered surface.	Sqm	457.40	16.60	7592.84
24.00	Finishing wall surface of walls with arcylic wall putty (Water based) of approved make and finished smooth and even surface toreceive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete	Sqm	268.85	71.40	19195.89
25.00	Wall painting 2 coats with Plastic paint of approved shade on new work over acoat of primer to give an even shade excuding cost of paint.	Sqm	268.85	76.40	20540.14
26.00	Painting two coat with any approved weather coat including cost,conveyance and taxes etc.complete.	Sqm	198.01	70.70	13999.31
27.00	Painting two coats with any approved paint over a coat of primer including cost cnoveyance and taxes etc. complete	Sqm	41.98	188.50	7913.23
28.00	Providing, fitting and fixing up window (sliding type) made up aluminum section 151 - 154, 155-154, as windows frame section No. 151-155, 151-153 and 151-167 as shouter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour t&P etc complete as per direction of EIC.	Sqm	12.73	3648.10	46440.31
29.00	Providing fitting, fixing of Al. door with OEL anodized Al. door section of 9202 as vertical member, 9201 as top member and 9200 as bottom and middle member and 6mm plain glass in top portion with 12mm thick pre-laminated board in bottom portion fixed on door frame by means of tapered clip No. 4660 and the frame to be completed by means of jointing angle No. 1855 including all cost of labour, T&P, hire charges of drilling machine, labour charges etc. complete.	Sqm	23.41	6231.62	145882.22
30.00	Labour for fixing big six or trafford GCI Sheet in roof including fixing of ridges wind tiles etc but excluding cost of fitting including drilling holes in wind ties.	Sqm	15.86	442.10	7011.71
31.00	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect.	Mtr	7.52	3495.10	26283.15
32.00	Fitting fixing of iron struss and angel for ac sheet for roof of ac sheet including all cost of material and labour	kg	91.80	70.00	6426.00
33.00	Supplying and laying & spreading and consolidation with HRR including watering , cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. completer as directed by the Engineer-in-charge	Cum	25.47	613.85	15634.76
34.00	Supplying and laying precast interlocking pavers block/concrete blockof 80 cm thick of approved design and filling the joint with sand complete as per MORD specifications(6:7)	Sqm	81.75	923.75	75516.56
				Rs	2195427.78

Total 34 (Thirty four) items only

My Quoted Rate is _____%(both figure and wards) Excess over/Less than/equal to the above Tender cost

-sd-
Chief Distirict Medical And Public Health Officer
Kalahandi