

FINANCIAL BID

Tender Inviting Authority: Special Officer, KKDA, LANJIGARH	
Name of Work: Construction of CHECKDAM WITH DIVERSION DRAIN AT DENGSGARGI	
BID Identification No:-01/KKDA/2021-22	
Bidder Name:	

SCHEDULE OF WORKS

Sl. No.	Description of work	Quantity	Unit	Estimated Rate	AMOUNT Rs. P
1	Excavation of foundation to proper profile in all kinds of soil with all leads and lifts including dressing and leveling the bed to proper slope and level making it fit for laying concrete including depositing the excavated materials clear of work site with all leads and lifts including dewatering from foundation if necessary complete as directed by the Engineer-in-charge.	418.94	1Cum	186.40	78090.00
2	Filling in foundation and plinth with excavated materials including watering and ramming as directed by the Engineer-in-charge.	139.66	1Cum	426.40	59551.00
3	Cement Concrete (1:3:6) using 40 mm size cbg metal including all cost, conveyance, royalty etc. complete.	17.76	1Cum	3919.00	69601.00
4	Cement concrete M15 grade with crushed granite coarse aggregate of 20 mm down graded mixed in concrete mixture including cost of all materials ,machineries and labourer with all lead for materials upto the mixing yard and transportation of mixed concrete within initial lead of 50m and laying in dams, barrages,power house and pen stock with all lift/delift upto 1.50m height above average ground level etc. complete in all respect to proper slope & level with all cost, conveyance, royalty & other taes of all materials complete in all respect as directed by the Engineer-in-charge.	282.50	1 cum	4247.30	1199862.00
5	Cement concrete M20 grade with crushed granite coarse aggregate of 20 mm down graded mixed in concrete mixture including cost of all materials ,machineries and labourer with all lead for materials upto the mixing yard and transportation of mixed concrete within initial lead of 50m and laying in dams, barrages,power house and pen stock with all lift/delift upto 1.50m height above average ground level etc. complete in all respect to proper slope & level with all cost, conveyance, royalty & other taes of all materials complete in all respect as directed by the Engineer-in-charge.	31.69	1 cum	4688.90	148591.00

Signature of Tenderer with seal

FINANCIAL BID

Tender Inviting Authority: Special Officer, KKDA, LANJIGARH	
Name of Work: Construction of CHECKDAM WITH DIVERSION DRAIN AT DENGSGARGI	
BID Identification No:-01/KKDA/2021-22	
Bidder Name:	

SCHEDULE OF WORKS

Sl. No.	Description of work	Quantity	Unit	Estimated Rate	AMOUNT Rs. P
6	Straightening, cutting, bending, binding and lying the grills as per approved design & placing in position including cost, conveyance of M.S. Rod & binding wire 18 to 20 gauge complete as directed by the Engineer-in-charge. (Weight of binding wire is not included for payment)	28.25	1 cum	5983.10	169023.00
7	Providing smooth centering, shuttering for R.C.C. work in F&P including cost, conveyance, royalty & all taxes of materials including dismantling it after required period etc. complete as directed by the Engineer-in-charge.	778.44	1 cum	108.08	84134.00
8	Earthwork in hard soil with 4 extra lead over initial lead of 50mtr and initial lift of 1.5m including rough dressing & breaking clods to maximum 5cm to 7 cm size & depositing the excavated materials in layers not exceeding 0.30mtr in depth etc complete and as directed by the Engineer-in-charge.	29.53	1 cum	155.30	4586.00
9	Rough stone dry packing in apron and revetment with hard granite stone of 15cm to 30cm in size for 1cum	72.90	1 cum	1207.20	88005.00
10	Supplying Fitting fixing of iron Channel including iron gate with locking system and all cost of fittings etc complete.	1.00	1 No	20000.00	20000.00
Total estimated cost in Figures					1921443.00
Rupees (Nineteen Lakh Twenty One thousand Four Hundred Forty Three) Only					

Approved for 10 items only

--sd--

Special Officer
KKDA, Lanjigarh

My Quoted tender is.....% Excess / Less (.....
..... Than the amount put to tender.

Signature of Tenderer with seal