

Tender Inviting Authority:CDM &PHO, Kalahandi, Bhawanipatna

Name of Work: Construction of Day Care Sub centre cum Health & Wellness Centre at Murshing of Narla block

Bid Identificatin No.:290/21.03.2022 of CDM &PHO,Kalahandi

Bidder Name:

SCHEDULE OF WORKS

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	unit	Quantity	Rate	Total amount with out taxes
1	2	3	4	5	6
1	Earth work in excavation of foundation in hard soil with all leads and lifts including dressing the sides and levelling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour and T&P,royalty etc. complete and as directed by the Engineer-in-charge.	cum	70.51	188.79	13311.58
2	Filling in foundation & plinth with sand in 22.5cm(9") thick layers including watering and ramming with all cost conveyance royalty, taxes of the materials and labour with T&P required for the work etc. complete or as directed by the Engineer-in-charge.	cum	103.51	293.70	30400.89
3	Plain Cement concrete (1:3:6) with 4cm size C.B, h.g metal of approved quality and from approved quarry including hoisting,lowering, and laying in layers to 10cm(4") thick to required level, ramming,watering including all cost & conveyance of all materials and labour with T&P required for the work with all taxes and royalties complete in all respects and as directed by the EIC.	cum	22.04	4402.40	97028.90
4	Fly ash brick masonry in cement mortar(1:6) for foundation and plinth after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge	cum	18.98	4083.40	77502.93
5	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying.				
6	(A) Column footings	cum	8.85	4805.25	42526.46

7	(B) plinth beam	cum	5.86	5161.02	30243.58
8	C)Column	cum	6.07	12010.37	72902.95
9	D)Beam	cum	6.19	12010.37	74344.19
10	(E) Lintel	cum	3.15	8354.09	26315.38
11	(f) Chajja	sqm	4.18	777.44	3249.70
12	(G) Shelves	sqm	12.05	727.57	8767.22
13	(H) Roof slab	cum	12.91	8971.07	115816.51
14	(I) Staircase	cum	1.37	10035.85	13749.11
15	Supplying fitting, with Straightening, cutting, bending, cranking, hooking, welding or jointing (if required) the HYSD steel and binding wires and binding, tying the grills, hoisting, lowering and placing in proper position as required for R.C.C. works and for providing cost, conveyance and taxes of M.S. rods or Tor steel including binding wires of 18 to 20 gauge and labour with all T&P required for the work etc. complete for ground floor or as directed by the Engineer-in-charge.	Qntl	54.68	9094.62	497293.82
16	Fly ash brick masonry in cement mortar(1:6) for superstructure after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as	cum	41.08	4121.72	169320.26
17	16mm thick cement plaster (1:6) over Brick / stone massonary finished smooth including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge	sqm	251.90	195.41	49223.78
18	12mm thick cement plaster (1:6) over Brick / stone massonary finished smooth including watering and curing with cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-	sqm	184.86	129.38	23917.19
19	20 mm thick Cement plaster in c.m.(1:6) over stone masonry including cost, conveyance, royalties, labour, T&P etc.complete.	sqm	27.31	205.12	5601.83
20	Supplying, fitting fixing of iron shutter M.S. panalled door single leaf with M.S. frame and M.S. panalled window double leaf with M.S. frame and grill etc. with all cost, carriage, taxes etc complete as directed by the EIC.	Kg	1627.91	72.20	117535.10

21	Fixing of Vitrified tiles in floors or treads on 25mm thick bed of cement mortar (1:1) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-charge.	sqm	101.89	900.39	91740.74
22	Fixing Ceramic tiles in dados skirting on 12mm thick CP (1:3) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect in all floors or as directed by the Engineer-in-	sqm	98.37	1049.26	103215.71
23	Supplying fitting fixing of granite tiles above 0.40sqm (20mm thick) in floors or treads on 25mm thick bed of cement mortar (1:4) jointed with net cement slury mixed with pigment to match the shades of the tiles including rubbing and polishing complete including cost of tiles all materials and labour with T&P required for the work with	sqm	6.47	1521.13	9841.71
24	White washing 3 coats with shell lime including cost of Lime etc conveyance, royalties and taxes of all materials and labour with T&P require for the work etc complete in all respect in all follrs or as directed by the EIC	sqm	535.86	16.80	9002.45
25	Finishing wall surface of walls with Acrylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete	sqm	326.40	72.26	23585.66
26	Wall painting 2 coats with Plastic paint of approved shade on new work over a coat of primer to give an even shade exculding cost of paint.	sqm	326.40	77.34	25243.78
27	Wall painting 2 coats with Weather coat of approved shade on new work to give an even shade including cost of paint etc conveyance, royalties and taxes of all materials and labour with T&P require for the work etc complete in all respect in all follrs or as directed by the EIC	sqm	177.51	71.67	12722.14
28	Painting 2 (Two) coats with any approved enamel paint over a coat of priming to new wood work and iron work including cost of the primer and paint sand papering polishing the surface with cost conveyance and taxes of all materials and labour with T&P required for the work etc. complete in all respect or as directed by the EIC.	sqm	79.08	191.47	15141.45

29	Providing, fitting and fixing up window (sliding type) made up aluminum section 151 - 154, 155-154, as windows frame section No. 151-155, 151-153 and 151-167 as shouter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour t&P etc complete as per direction of EIC.	sqm	3.07	3669.94	11266.72
30	Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all	mtr	7.32	3499.54	25616.63
31	Labour for fixing big six or trafford GCI Sheet in roof including fixing of ridges wind tiles etc but excluding cost of fitting including drilling holes in wind ties.	sqm	13.27	445.11	5906.61
32	providing , staging & spreading of moorum & consolidation with HRR including watering , cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. completer as directed by the Engineer-in-charge	cum	42.45	622.46	26423.43
				Total in Figures Rs.	1828758.39
Total 32 items				Or say	1828758.00
My quoted Rate is					
_____ % (both in figure and words) .					
excess over/less than/equal to the above Tender cost					

s/d
Chief District Medical & Public Health Officer
Kalahandi