

Tender Inviting Authority:CDM &PHO, Kalahandi, Bhawanipatna					
Name of Work: Construction of Maa gruha at CHC Th Rampur					
Bid Identification No.:290/21.03.22 of CDM & PHO Kalahandi					
Bidder Name					
SCHEDULE OF WORKS					
SI NO	Item Description	Unit	Quantity	Quoted Rate (Rs.)	
				Rate	Amount
1.00	Earth work in excavation of foundation in hard soil including dressing and leveling the bed and depositing the soil within 50 m initial lead and 1.5 m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3 m in depth and as per direction of the Engineer-in-charge.	Cum	145.58	188.79	27484.05
2.00	Filling foundation and plinth with sand well watered and rammed including all cost, conveyance, royalties, labour etc. complete.	Cum	156.21	293.17	45796.09
3.00	Cement concrete (1:3:6) using 4cm size h.g.metal including all cost, conveyance, royalties etc. complete.	Cum	51.70	5349.66	276577.42
4.00	Fly ash brick masonry in cement mortar(1:6) for foundation and plinth after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge	Cum	43.87	4847.36	212653.68
5.00	R.C.C. work of M-20 grade with 20mm and down grade black hard granite (crusherbroken) stone chips including hoisting and laying.				0.00
6.00	Column base	Cum	12.88	5776.42	74400.29
7.00	Grade beam	Cum	6.23	6132.19	38203.54
8.00	Coloumn and beam	Cum	8.96	12981.54	116314.60
9.00	Lintel	Cum	2.73	9325.26	25457.96
10.00	Chajja	Sqm	6.25	840.57	5253.56
11.00	Shelves	Sqm	1.92	771.28	1480.86
12.00	Roof Slab	Cum	14.67	9942.24	145852.66
13.00	Supplying, fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification including cost, conveyance and taxes of all materials.	Qtl	50.99	9157.77	466954.69
14.00	Plain Cement concrete (1:2:4) using 12mm size c.b.h.g.chips including cost, conveyance and royalty etc complete.	Cum	13.92	6704.02	93319.96
15.00	Fly ash brick masonry in cement mortar(1:6) for superstructure after immersing bricks for six hours in water before use work of size (23 x 11 x 8 cm) having a crushing strength of not less than 75 Kg/Cm ² including splays cutting circular moulding chmfering and corbelling watering and curing et complete including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete in all respect or as directed by the Engineer-in-charge	Cum	37.65	4885.69	183946.23
16.00	16 mm thick cement plaster in c.m.(1:6) over brick works including cost, conveyance, royalties, labour, T&P etc. complete.	Sqm	169.48	210.50	35675.54
17.00	12 mm thick Cement plaster in c.m.(1:6) over stone masonry including cost, conveyance, royalties, labour, T&P etc. complete.	Sqm	195.09	141.90	27683.27
18.00	Supplying iron shutter M.S. panalled door single leaf with M.S. frame and M.S. panalled window double leaf with M.S. frame and grill etc. with all cost, carriage, taxes etc complete as directed by the EIC.	kg	1337.80	72.20	96589.16
19.00	Fixing of Vitrified tile in floors of size 600mmX600mm on 25mm thick in c.m.(1:1) joints with neat cement slurry mixed with pigment to match the shades of the times including rubbing & polishing etc. complete.	Sqm	95.69	937.78	89736.17
20.00	Fixing of ceramic tiles in dadoes including skirting dadoes with 12mm thick c.p. in c.m.(1:3) jointed including cost, carriage, labour etc. complete.	Sqm	91.85	1084.40	99602.14
21.00	White washing 3 coats with shell lime over plastered surface.	Sqm	464.89	16.80	7810.15

22.00	Finishing wall surface of walls with arcylic wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes, labour T&P etc complete	Sqm	192.29	75.74	14564.04
23.00	Wall painting 2 coats with Plastic paint of approved shade on new work over a coat of primer to give an even shade excluding cost of paint.	Sqm	192.29	77.36	14875.55
24.00	Painting two coat with any approved weather coat including cost, conveyance and taxes etc. complete.	Sqm	237.02	71.67	16987.22
25.00	Painting two coats with any approved paint over a coat of primer including cost conveyance and taxes etc. complete	Sqm	85.62	191.47	16393.66
26.00	providing , staging & spreading of moorum & consolidation with HRR including watering , cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc. complete as directed by the Engineer-in-charge	Cum	70.41	622.46	43827.41
				Rs	2177439.90

Total 26 (Twenty six) items only

My Quoted Rate is _____ % (both figure and wards) Excess over/Less than/equal to the above Tender cost

-sd-

**Chief District Medical And Public Health Officer
Kalahandi**