

OFFICE OF THE PANCHAYAT SAMITI BHAWANIPATNA, KALAHANDI

NOTICE INVITING TENDER

Bid Identification No. 01 2018/19

Letter No. 1377

Date: 21-04-18

The BDO Bhawanipatna on behalf of Governor of Odisha invites percentage rate bids in single cover system for the construction of works as described in the DTCN.

1. Nature of work: Construction of Concrete Drying Platform cum Threshing Floor at different Villages
2. Number of works : 18 (Eighteen)
3. Estimated Cost : Rs 06,47,800.00
4. Period of completion : Two Calendar months
5. Sale of Tender documents : 07 hours of 23.04.2018 to 13 hours of 07.05.2018
6. Last Date of receipt of Tender Documents: 14 hours of 07.05.2018
7. Date of Opening of the Bid : 11 hours of 09.05.2018

Further , the details tender documents (DTCN) can be had from the Office of Block Development Officer , Bhawanipatna and from the District portal [www.kalahandi.nic.in](http://www.kalahandi.nic.in) within the mentioned time period.

  
Block Development Officer  
Bhawanipatna

Memo No. 1378 Dated - 21-04-18

Copy to All Executive Engineers of Kalahandi district / all E.O.s of Municipality/NAC for information and necessary action. They are requested to display the notice in the notice board for wide publication.

  
Block Development Officer  
Bhawanipatna

Memo No. 1379 Dated. 21-04-18

Copy forwarded to the DIO, NIC Kalahandi for information and necessary action . He is requested to web host the tender document in the district portal.

  
Block Development Officer  
Bhawanipatna

Memo No. 1380 Dated 21-04-18

Copy to Advertisement Manager Sambad/Dharitri/Orissa Post Bhubaneswar for kind information and necessary publication in daily

  
Block Development Officer  
Bhawanipatna


# PANCHAYAT SAMITI OFFICE, BHAWANIPATNA

## DETAILED TENDER CALL NOTICE

Bid No. 01 /2018-19

Sealed Percentage Rate Tenders are invited from the registered "C" & "D" Class contractors registered with the State Government and contractors of equivalent grade of other State / C.P.W.D / M.E.S. / Railways / in single cover system for the works detailed in the table 1 attached. The bid documents must incorporate scanned copy of registration certificate, E.M.D. at 1% of the bid value, valid TIN/SRIN No. , Valid GSTIN number , valid PAN No., works experience certificate, no relation certificate etc. in conformity, with DTCN.


1. Bid documents consisting of estimates, specification, schedule of quantity, plan and a set of terms and conditions can be had from the Block Development Officer, Bhawanipatna on payment of **RS. 4000/-** by cash or Demand Draft duly pledged in favour of Block Development Officer, Bhawanipatna payable at Bhawanipatna.
2. Bid documents consisting of plans, specifications, schedule of quantity, plan and a set of terms and conditions of contract and other necessary documents can be seen in all the offices issuing the documents and office of the undersigned during office hours every day except Sundays and Public holidays till last date of sale and receipt of tender papers. Interested bidders may obtain further information at the same address.
3. Bid must be accompanied by earnest money deposit / Bid Security of the amount specified for the work in the table SI.1 payable at any Nationalized Bank duly pledged in favour of Block Development Officer, Bhawanipatna payable at Bhawanipatna and will have to be in any one of the forms as specified in the bidding documents.
4. The sale and receipt of the Bid documents shall starts from **7 hours of 23.04.2018** and closed on **14 hours of 07.05.2018** . Bids shall be received in the office where the bids have been notified to be sold.
5. Bids must be delivered in the tender box having Identification **No. 01/PR /Bhawanipatna**.
6. Bids received shall be opened at **11:00 AM on 09.05.2018** in the Office of Block Development Officer, Bhawanipatna in presence of the bidders who wish to attend. If the office happened to be closed on the last date of opening of the bids as specified, the bids will be opened on the next working day at the same time and venue.
7. Bidding documents requested by mail will be dispatched by registered / speed post on payment of an extra amount of Rs. 5000.00 over the cost of documents. The authority will not be held responsible for the postal delay in any, in the delivery of the documents or non-receipt of the same.
8. Submission of more than one tender by a bidder for a particular tender will be liable for rejection of all such tender papers.
9. Other details can be seen in the bidding documents.
10. The authority reserves the right to cancel any or all bids without assigning any reason.

  
Block Development Officer  
Bhawanipatna

**Table 1**  
**SCHEDULE OF WORK**

Sl no	Name of the Work	Approximate Value of work (in Rs)	Period of completion	Class of contractors	EMD @1%	Cost of Bid document
1	2	3	4	5	6	7
1	Const of Concrete Drying Platform cum Threshing Floor at Dangapakhan GP Gurjung	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
2	Const of Concrete Drying Platform cum Threshing Floor at Gurjung GP Gurjung	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
3	Const of Concrete Drying Platform cum Threshing Floor at Jugsaipatna GP Jugsaipatna	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
4	Const of Concrete Drying Platform cum Threshing Floor at Kukuti GP Seinpur	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
5	Const of Concrete Drying Platform cum Threshing Floor at Dumuria GP Dumuria	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
6	Const of Concrete Drying Platform cum Threshing Floor at Chheliamal GP Chheliamal	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
7	Const of Concrete Drying Platform cum Threshing Floor at Gudialipadar GP Gudilaipadar	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
8	Const of Concrete Drying Platform cum Threshing Floor at Ghurigudi GP Palsijharan	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
9	Const of Concrete Drying Platform cum Threshing Floor at Gachhkhola GP	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-

	Udeypur					
10	Const of Concrete Drying Platform cum Threshing Floor at Dangripadar GP Thuapadar	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
11	Const of Concrete Drying Platform cum Threshing Floor at Jamunasagar GP Duarsuni	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
12	Const of Concrete Drying Platform cum Threshing Floor at Kusumdar GP Malgaon	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
13	Const of Concrete Drying Platform cum Threshing Floor at Nakjhari GP Sagada	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
14	Const of Concrete Drying Platform cum Threshing Floor at Kuliamal GP Kuliamal	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
15	Const of Concrete Drying Platform cum Threshing Floor at Bhawanipur GP Medinipur	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
16	Const of Concrete Drying Platform cum Threshing Floor at Salebhata GP Gudialipadar	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
17	Const of Concrete Drying Platform cum Threshing Floor at Chahagaon GP Chahagaon	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-
18	Const of Concrete Drying Platform cum Threshing Floor at Salegaon GP Sikuan	Rs. 6,47,800.00	Two calender Months	"D" or "C"	Rs 6480/-	Rs 4000/-

  
 Block Development Officer  
 Bhawanipatna

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Dangapakhan G.P. Gurjung Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantaling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26


Total 647809.15

( Say six lakh forty seven thousand eight hundred only)

say 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

  
Addl. P.D (Tech.)  
DRDA, Kalahandi  
26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Gurjung G.P. Gurjung Bhawanipatna Block**


Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
Total					647809.15

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved  
  
Addl. P.D (Tech.)  
DRDA, Kalahandi  
26.3.18


**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Jugsaipatna G.P. Jugsaipatna Bhawanipatna Block**


Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
<b>Total</b>					<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved  
  
Addl.P.D (Tech.)  
DRDA, Kalahandi  
26-9-18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Kukuti G.P. Seinpur Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26

Total 647809.15

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved  
26.3.18  
Addl.P.D (Tech.)  
DRDA, Kalahandi

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Chheliamal G.P. Chheliamal Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>


( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved

  
Addl.P.D (Tech.)  
DRDA, Kalahandi

26-3-18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Dumuria G.P. Dumuria Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantaling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved  
Addl.P.D (Tech.)  
DRDA, Kalahandi

26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Gudialipadar G.P. Gudilaipadar Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block



  
Addl.P.D (Tech.) 26.3.18  
DRDA, Kalahandi

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Ghusurigudi G.P. Palsijharan Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				Total	647809.15

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved

Addl.P.D (Tech.)  
DRDA, Kalahandi

26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum  
Threshing Floor" at Gachkhola G.P. Udeypur  
Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

*Approved*

  
Addl. P.D (Tech.)  
DRDA, Kaichandi 26.8.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Dangripadar G.P. Thuapadar Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26

Total 647809.15


( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved

  
Addl. P.D (Tech.)  
DRDA, Kalainaraj

26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Jamunasagar G.P. Duarsuni Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved  
Addl.P.D (Tech.)  
DRDA, Kaiahandi

26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Kusumdar G.P. Malgaon Bhawanipatna Block**


Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approve  
  
Addl. P.D (Tech.)  
DRDA, Kalahandi  
26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Nakjhari G.P. Sagada Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
<b>Total</b>					<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

*Approved*

  
Addl. P.D (Tech.)  
DRDA, Kalahandi

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Kuliamal G.P. Kuliamal Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved  
Addl.P.D (Tech.)  
DRDA, Kalahandi

26.3.18

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Bhawanipur G.P. Medinipur Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved  
  
Addl.P.D (Tech)  
DRDA, Kalahandi

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Salebhata G.P. Gudialipadar Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst. Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block


Approved  
  
Addl.P.D (Tech.)  
DRDA, Kapanandol

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Chahagaon G.P. Chahagaon Bhawanipatna Block**


Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
				<b>Total</b>	<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

  
Asst/ Executive Engineer  
Bhawanipatna Block

  
Block Development Officer  
Bhawanipatna Block

Approved  
  
P.D. (Tech.) 26.3.16  
Chahandi

**Bill of Quantity for the work " Const of Concrete Drying Platform cum Threshing Floor" at Salegaon G.P. Sikuan Bhawanipatna Block**

Sl. No	Item	Quantity	Unit	Rate	Amount
1	Earth work excavation for foundation in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete	27.24	%cum	12795.8	3485.58
2	Collecting, supplying and filling of sand in foundation and plinth including watering and ramming etc complete	104.46	Cum	323.5	33792.81
3	Plain cement concrete (1:3:6) using 40mm size CBG metal including labour and all cost , carriage and royalty etc complete	84.03	Cum	3699.1	310835.37
4	12mm thick cement plaster using C:M(1:6) including labour and all cost , carriage and royalty etc complete	52	Sqmt	96.5	5018.00
5	Rigid smooth centering and shuttering for RCC work including false work and dismantling then after casting including of all carriage , cost of wooden materials atc complete (For Mass Concrete)	96	Sqmt	85.8	8236.80
6	CC (1:2:4) using 12mm size crusher broken granite chips including labour and all cost , carriage and royalty etc complete	42.4	Cum	4845.8	205461.92
7	Supplying, fitting and placing uncoated HYSD bars reinforcement including cost , conveyence and all taxes of steel and binding wire 18 to 20 gauge etc complete	12.72	Qntl	6215.52	79061.41
8	Earth work in hard soil within 50mt initial lead and 1.5mt initial lift including rough dressing and levelling the bed etc. complete for backfilling of trench 2/3rd of item -1	18.16	%cum	10557.58	1917.26
<b>Total</b>					<b>647809.15</b>

( Say six lakh forty seven thousand eight hundred only)

say Rs 647800.00

Asst. Executive Engineer  
Bhawanipatna Block

Block Development Officer  
Bhawanipatna Block

Approved  
Addl.P.D (Tech.)  
DRDA, Kalahandi

26.3.18

## Instruction to bidders/ tenderers

(This will form a part of contract at the time of drawl of agreement)

1. The contractor desiring to submit tenders should be registered under Odisha State PWD / CPWD / Railways / MES having experience on construction of road and building works in conformity with detailed tender call notice for execution of the works on drawl of agreement in P1 contract forms of Government of Odisha. The bidder should have been registered with the Government of Odisha / other State Government. The successful bidder with outside State Government license will have to register them under the Government of Odisha within one month of acceptance of bid in case of licensing authorities other than Odisha State.
2. Earnest money deposit : 1% (one percent) of the estimated cost rounded up to nearest hundred rupees in shape of P.O.S. / P.O.T.D. / N.S.C. / K.V.P. / Short term deposit / deposit receipt of any schedule Bank duly pledged in favour of Block Development Officer, Bhawanipatna
3. The following documents / certificates and instruments should be furnished along with the tender papers.
  - (i) EMD as specified in the tender call notice
  - (ii) Copy of contractor's registration certificate
  - (iii) Copy of valid PAN card, GSTIN number, no relation certificate.
  - (iv) Submission of more than one tender paper by a tenderer for a particular work will be liable for rejection of all such tender papers.
  - (v) The bidder has to produce an affidavit in support of the authenticity of the documents including the POSB / POTD/ NSC/ KVP etc. attached with the bid
4. Additional performance security (A.P.S.)

As per amendment to para 3.5.5 (V) of note II of PWD code , Vol-1 by modification vide office memorandum No 5288 dated 04.05.2016 of works Department , Government of Odisha. The additional performance security should be furnished by the bidder when the bid amount is less than the estimated cost put to tender. In such an event the bidder who has quoted less bid price / rates than the estimated cost put to the tender minus the quoted amount as additional performance security in shape of Term Deposit Receipt pledged in favor of the Block Development Officer, Bhawanipatna in the sealed envelope along with the price bid at the time of submission of the bid.
5. When the bid amount is less than the estimated cost by more than 10% and within 15% in such an event, the successful bidder will deposit the APS to the extent of 1.5 times of the differential cost of the bid amount and 90% of the estimated cost.
6. Security deposit will be recovered @5% of the gross amount of the work bills of 'B' class and above contractors and @3% of 'C' & 'D' class contractors which will be refunded after twelve months of actual date of completion subject to final bill is paid.
7. Income tax, cess, octroi, royalty etc. and any other tax which has been or to be levied by the government will be recovered as per Government rules at prescribed rates.

8. The clause No. 2(b) (i) & (ii) of standard F2 form (now P1) which is a part of contract are deleted and the following amendments are made:  
In case the contract is rescinded then 20% of the cost of left out work will be imposed as penalty which can be recovered from any dues of the contractor lying under this department or other department of the Government of Odisha.
9. Penalty may be imposed on the contractor in case he fails to complete the work within stipulated date of completion which will be calculated @10% of the contract value.
10. The Engineer contractors desirous of availing exemption of EMD/SD are required to submit an affidavit as regards fact of the number of awarded works during the current financial year without submission of EMD/SD. The Engineer contractor can submit tenders without EMD up to three works only including the previously awarded cases. Tenders more than three works should be submitted with EMD otherwise the tenders will be rejected.
11. Scheduled caste / Schedule tribe contractors desirous of availing preference 10% on the lowest tendered amount should submit copy of the affidavit for the same along with tender document otherwise their claim may not be taken into account after opening of tenders.
12. EMD must be pledged in favour of Block Development Officer, Bhawanipatna. Tenders with unpledged EMD or EMD pledged to other than the Block Development Officer, Bhawanipatna will be rejected. Requested for adjustment of EMD of some other works will not be considered.
13. The Engineer contractor cannot give power of attorney to some other person for submitting the tender or for execution of work.
14. The contractors desirous of executing power of attorney with some other person for execution of works should be registered with Registrar / Sub-Registrar.
15. The contractors desirous of executing the work through his power of attorney should submit an affidavit that the power of attorney will be valid till satisfactory completion of work or the department should be intimated in writing as regards revocation of power of attorney intermediate period before completion of work. Executing the work through power of attorney shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts/defaults of the attorney during the course of execution of work.
16. The contractor should provide original copies of the above document at the time of signing the agreement along with VAT clearance certificate, original license of registration.
17. The rate quoted in the tender schedule is the estimated rates calculated by the department. The contractors should submit his rates quoting percentage in excess/equal/less to the said rates as per his calculation taking into consideration the site condition anticipating the labour and materials rates, taxes & royalties etc. to be paid by him during execution of works.

18. In case the rates of royalty changed by the Government this will come into force from the date of order of Government and the same is binding on the contractor. The Department will not compensative enhanced cost of royalty to the contractor.
19. Service tax and other taxes as made applicable by Government will be borne by the contractor and Department will not compensate it.
20. The contractor should carry out the work as per instruction of the Principal, Extension Training Centre, Bhawanipatna/ Assistant Executive Engineer, Bhawanipatna/ Jr. Engineer, Bhawanipatna in charge of the work and any dispute at site of the work should be brought to the notice of the Principal, whose decision is final.
21. The contractor is bound to abide by all the codal provisions of OPWD and all the amendments thereof.
22. The tender is valid for 90 days from the date of opening of the tender. However, validity of tender can be extended if agreed by contractor as well as the undersigned.
23. The contractor cannot sublet the whole or part of the work without written consent of the undersigned.
24. The contractor should submit a work programme at the time of signing the agreement for timely completion of work.
25. The contractor shall abide by "fair wages" clause in accordance with the Government of Odisha, Works and Transport Department letter No. A-VIIIR R 18/52/25 dated 26/02/1955 and No. 11M-56-51-28845(A) date 27/09/1961 and Workmen's compensation act 1923 and other laws as may be introduced by the Government from time to time.
26. On completion of the work all rubbish, debris, vats, temporary structures of any sort are to be removed by the contractor from the site of work and all pits, excavation filled up at this own cost and the site is handed over in a tidy and workmen like condition.
27. The Executive Engineer shall make any variation of the form, quality and quantity of the works or any part thereof that may in his opinion be necessary. The extract items will be paid to contractor as per prevailing schedule of rates.
28. The rate in the tender will be deemed to include cost of all materials including loading, unloading, leads, lift, taxes, royalty and any other charges for satisfactory completion of work.
29. Any defects, shrinkage or other faults which may be noticed during the defect liability period should be made good or rectified by the contractor at his own cost.

30. If at any time after commencement of the work the Department does not require the whole or any part of the work as specified in contract to be carried out, the PRINCIPAL, shall give notice in writing to the contractor who shall have no claim to any payment of compensation what so ever on account of profit or advantage which he might have derived from the execution of the portion of work.
31. The contractor shall take all precaution for safety of the workers and preserving their health and arrange necessary insurance converge for any losses of life/ Personal injury for which Department will no way be responsible for such event.
32. If the lowest bidder doesn't turn up for agreement after finalization of the tender, then he shall be debarred from participation in bidding for three years and action will be taken to blacklist.
33. A quarry chart as may be available may be seen in the office of Block Development Officer, Bhawanipatna. The contractor however must satisfy himself those materials as per required specification and quantities are available in those quarries. No extra payment will be made if required quantities in the quarries shown in the Department quarry chart are not available. The quarry chart is only an information and Department does not accept the responsibility if the material are not available in full quantity and quality. The contractor would, however, be responsible for procurement of materials from authorized sources and voluntarily disclose the source of procurement for the purpose of billing.
34. If the tenderer withdraws his bid/tender before the expiry of the validity period of tender or makes any modification in the tender and condition of the tender, EMD shall stand forfeited.
35. Joint venture / Consortium agreement / M.O.U. are not allowed to participate in tender.
36. The undersigned reserves the right to reject any tender without assigning any reason thereof.

Sd-  
Block Development Officer  
Bhawanipatna