

BID IDENTIFICATION NO. JAIPATNA BLOCK, KLD- 01 /2018-19



GOVERNMENT OF ODISHA

PANCHAYATI RAJ & DRINKING WATER DEPARTMENT

(Civil Works)

DETAILED TENDER CALL NOTICE FOR THE WORK:

| Sl No. | Name of the Project | Estimated Cost |
|--------|---|------------------|
| 1 | Construction of Box Cell Culvert on the road from School pada (Nagupada) to Sadargudi (Nagupada) | RS. 41,89,026.00 |
| 1 | Construction of New ICDS Building at Jaipatna, GP. JAIPATNA | RS. 19,21,418.00 |

Contractor

BDO

Page | 1

OFFICE OF THE PANCHAYAT SAMITI JAIPATNA, KALAHANDI

BID IDENTIFICATION No: JAIPATNA BLOCK, KLD / 01 / 2018-19

No . 01/ Jpt/ Dtd.

The BDO JAIPATNA on behalf of Governor of Odisha invites **Percentage Rate** bids in single cover system for the construction of works as detailed in the table, from the class of eligible contractors as mentioned in column-5 (five) registered with the State Governments and Contractors of equivalent Grades / Class Registered with Central Government / MES / Railways, to be eventually drawn up in PWD P-1 **Agreement** form, for execution of Buildings i.e. **civil works**. The proof of registration from the appropriate authority shall be enclosed along with the Bid. If successful, the bidder who has not registered under state government has to register under the state PWD in appropriate class of eligibility before signing of the agreement. The bidders may submit bids for the following work.

TABLE -1

| Sl no | Name of the Work | Approximate Value of work (In Rs.) | Period of completion | Class of contractor | EMD Bid security @ 1% | Cost of Bid document |
|-------|---|------------------------------------|----------------------|---------------------|-----------------------|----------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Construction of Boxcel culvert on the Road from School pada (Nagupada) to Sadargudi(Nagupada) GP- PKMUNDI, Jaipatna Block | 41,89,026.00 | Four Calendar Month | B & A | 42,000.00 | 6000.00 |
| 2 | Construction of New ICDS Building at Jaipatna, GP. JAIPATNA | 19,21,418.00 | Four Calendar Month | D & C | 20,000.00 | 6000.00 |

1. Bid documents consisting of plans, specification, the schedule of quantities and the set of terms & conditions of contract and other necessary documents can be seen in the office of the undersigned during office hours every day except on Sunday & Public holidays till last date of sale and receipt of tender paper. The Bid documents will also be available in the district website <http://kalahandi.nic.in> from Date **26.11.2018 11 AM to 06.12.2018 5PM**.

Contractor


BDO 24/11/18 Page | 2
Block Development Office
Jaipatna

2. Bids must be accompanied with E.M.D. (Bid Security) of the amount specified for the work in the table Col.6 above in shape of N.S.C./P.O.T.D / Post Office Savings Pass Book / Deposit receipt of any Scheduled Bank (Valid minimum one year from the date of receipt) duly pledged in favour of BDO JAIPATNA. Bidders desirous to hire machineries or equipments from outside of the State are required to furnish 2% of the amount put to tender as bid security instead of 1%. Bids without E.M.D. or in other shape will not be considered and liable for rejection.
N.B:- E.M.D. in shape of Cash / Pay Orders or Bankers Cheques / Bank Draft is not acceptable.
3. The sale of the Bid document shall start from Dt. 26.11.2018 at 11 AM and close on Dt. 06.12.2018 at 5.00 P.M. during office hours in the office of the under signed. The Tenderers delivered the tender documents along with the relevant documents of one work in the sealed cover with caption the name of the work over the envelop. Bids shall be received through Registered Post/ Speed Post with AD, on or before Dt.10.12.2018 at 5.00 P.M. The authority will not be held responsible for any Postal delay in delivery of the Bid documents or non-receipt of the same.
4. The Bid will be opened on Dt.12.12.2018 at 11.00 A.M. in the office of the undersigned in the presence of the members of the Block Level Tender/Purchase Committee and the bidders or their authorised representative. If the office happens to be closed on the date of receipt / opening of the bids as specified, above will be received / opened on the next working day at the same time and venue.
5. Bid documents can be purchased from this Agency on payment of the tender cost mentioned against the work in Col. 7 in shape of cash or DD drawn in favour of BDO JAIPATNA payable at KALAHANDI from any Nationalized scheduled Bank towards cost of tender paper. This is non-refundable.
6. The tender documents can be downloaded from district website <http://kalahandi.nic.in> on payment of tender cost of Rs 6,000/- (Rupees Six Thousand Only) each set in shape of Demand Draft in favour of BDO JAIPATNA and submit the Demand Draft in a separate envelope marked "COST OF TENDER DOCUMENT DOWNLOADED FROM INTERNET" alongwith the tender.
7. Balance Bid security @ 1% of contract value shall be pledged in parts in favour of BDO JAIPATNA corresponding to the respective value of works and deposited during drawl of agreement.
8. Bidders shall submit original affidavit regarding authenticity of their documents and E.M.D along with their bids. Bids shall be accompanied with attested true copy of valid registration certificate, valid GST clearance certificate and PAN card, otherwise his/her bids shall be declared as non-responsive and thus liable for rejection. The original certificates of the lowest three bidders are to be produced before Executive Engineer, DRDA, KALAHANDI for verification.
9. Other details can be seen in the bidding documents.
10. Checklist is to be duly filled in.
11. Engineer Contractors desirous to avail the facility of exemption of E.M.D. is required to submit an affidavit to the effect that he has not yet availed the facility for more than two works during the current financial year. The name of work for which and the authority to which the tender is being submitted must be mentioned in the affidavit failing, which the tender will be rejected.

Contractor


BDO
Block Development Office
Jaipatna

Page | 3

12. The ST/SC contractor desires to avail price preference are required to submit an affidavit.
13. The name of work for which and the authority to which the tender is being submitted must be mentioned in the affidavit failing which the tender will be rejected.
14. Additional Performance Security shall be obtained from the bidder when the bid amount is less than estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as additional performance Security (APS) in shape of Term Deposit Receipt pledged in favour of Divisional Officer/Bank Guarantee in favour of the Divisional Officer from any Nationalized/Scheduled Bank in India. Counter guaranteed by its local branch at Block within seven days of issue of Acceptance (LoA) BY THE Divisional Officer (by e-mail) to the successful bidder otherwise the bid of the successful bidder shall be cancelled and the Earnest Money Deposit/Bid Security shall be forfeited. Further proceeding for blacklisting shall be initiated against the bidder.
15. Any corrigendum / Addendum will be displayed in the website <http://kalahandi.nic.in> only.
16. Conditional tender will summarily be rejected.
17. Building and other Construction Workers Welfare Cess @ 1% (One Percentage) of the cost of construction shall be deducted from bills.
18. Rate shall be putted in percentage both in figure and word writing excess or less into one decimal point shall be considered in next round off.
19. The items covered in Clause No- 147 of DTCN are required as essential criteria for eligibility for qualification.
20. The authority reserves right to reject any or all the bids without assigning any reason thereof.

Sd
Block Development Officer
JAIPATNA Block

Memo No 2473 Dt. 24.11.2018

Copy to The Editor , The Sambad Bhubaneswar, The Dharitri Bhubaneswar, The Samaj and The India Post, Bhubaneswar for advertisement in there News-paper. He should submit a copy of advertisement along with bill limited to Rs 5,000/- for payment of advertisement charges. It is requested to get the tender notice published consuming size 10 cm x 10 cm space, before Dt...06.12.2018 in one issue only for wide publication. The complementary copies for the same may please be sent to this office for reference and record.

Sd/-
Block Development Officer
JAIPATNA Block

Memo No 2474 Dt. 24.11.2018

Copy along with soft copy of the notice submitted to the D.I.O., NIC, Kalahandi with a request to display the Tender call Notice and Tender document in the Web-site till 5 PM ofdt 06.12. 2018 Enclose:-Soft copy 1 no.

Sd/-
Block Development Officer
JAIPATNA Block


BDO
Block Development Office
Jaipatna

Page | 4

Contractor

Memo No. 2475 / Dt. 24.11.2018

Copy submitted to the Collector cum District Magistrate, Kalahandi / Superintendent of Police/ OIC
JAIPATNA Police Station , Kalahandi for kind information and necessary action.

Sd/-

Block Development Officer
JAIPATNA Block

Memo No. 2476 Dt. 24.11. 2018

Copy to Notice Board of Block office for wide circulation.

Sd/-

Block Development Officer
JAIPATNA Block

Tender Inviting Authority:- Block development Officer, JAIPATNA

| Name of the Work:- | | Construction of New ICDS Building at Jaipatna | | | |
|---|--|--|-----------------|-----------------------|---------------|
| Class of Contractor: 'C' & 'B' | | E M D 1% of estimated Cost | | | |
| Bid Identification no;-01 | | Estimated cost put to tender:-19,21,418.00 | | | |
| Bill of Quantities | | | | | |
| SI No | Description of works | Unit | Quantity | Estimated Rate | Amount |
| 1 | Earth work in excavation of foundation & plinth in hard soil including dressing of sides and levelling the bed up to the required depth and depositing the excavated materials away from the work site within 50m initial lead & 1.5m initial lifts with sundries & T&P required for the work complete including cost of all labour,labour cess,T&P,sundries etc. as directed by the Engineer in charge. | cum | 75.37 | 134.43 | 10132.00 |
| 2 | Filing foundation and plinth with sand of approved quality from approved quarry with all leads and lifts, well watered and rammed to required depth including cost, conveyance, royalty, all taxes of materials, labour charges, T&P etc. complete as per specification and direction of Engineer-in-charge but excluding GST. | cum | 132.42 | 325.10 | 43050.00 |
| 3 | Cement Concrete(1:3:6) using 40 mm size crusher broken hard HG metal, sand and cement of approved grade and quality from approved quarry in foundation including all cost, carriage, royalty taxes etc. complete including mixing, hoisting, lowering, laying and compacting to required thickness in layers of 15 cm depth, curing for required period including cost of labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | cum | 20.97 | 3401.20 | 71323.00 |
| 4 | CB Brick masonry in cement mortar (1:6) in Foundation and Plinth using 23X11X8 mm size fly ash bricks having crushing strength 75 kg / Cm2 with sharp edges and uniform size, sand and cement of approved grade and quality from approved quarry conforming to relevant codes including wetting the bricks, laying in layers with cement mortar of right proportion, providing scaffolding if required including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | cum | 18.08 | 3166.10 | 57243.00 |
| 5 | Reinforced Cement Concrete in M20 using 20 mm size and down graded hard granite chips, sand and cement of approved grade and quality conforming to relevant codes from approved quarry with all leads and lifts including mixing in right proportion, hoisting, lowering, laying in layers not exceeding 15 cm in thick and compacting by means of vibrator to required density, line, grade and camber including providing centering and shuttering and curing for required period including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | cum | 64.69 | 4033.30 | 260914.00 |
| 6 | CB Brick masonry in cement mortar (1:6) in Super Structure using 23X11X8 mm size fly ash bricks having crushing strength 75 kg / Cm2 with sharp edges and uniform size, sand and cement of approved grade and quality from approved quarry conforming to relevant codes including wetting the bricks, laying in layers with cement mortar of right proportion, providing scaffolding if required including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | Cum | 56.22 | 3199.10 | 179853 |

| | | | | | |
|----|---|-------|--------|---------|-----------|
| 7 | Providing 12 mm thick cement plaster(1:6) cement mortar using sand and cement of approved grade and quality from approved quarry with all leads and lifts conforming to relevant codes including mixing the ingredients in right proportion placing in position and finishing smooth to correct line and grade including providing scaffolding and cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | sqmt | 167.18 | 98.20 | 16417.00 |
| 8 | Providing 16 mm thick cement plaster(1:6) cement mortar using sand and cement of approved grade and quality from approved quarry with all leads and lifts conforming to relevant codes including mixing the ingredients in right proportion placing in position and finishing smooth to correct line and grade including providing scaffolding and cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | Sqmt | 567.78 | 140.40 | 79716.00 |
| 9 | Straightening bend up or coiled rod cutting, bending, cranking, hooking, welding or jointing (if required) the M.S. Rods or Tor steel and binding wires and binding, tying the grills, hoisting, lowering and placing in proper position as required for R.C.C. works including cost, conveyance and taxes of M.S. Rods or Tor steel and binding wires of 18 to 20 gauge and labour with all T&P required for the work etc.complete in all floors (weight of binding wires will not be considered for payment and payment will be made on weight of M.S. rods or Tor steel only) as per direction of the Engineer-in-charge. | Qtl | 71.16 | 6407.77 | 455977 |
| 10 | Providing rigid and smooth centering and shuttering for RCC works for Beams, columns, girder and bressmer including cost, conveyance, royalties, all taxes, of all materials with all leads and lifts, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | | | | |
| A | Lintel Band | sqmtr | 25.91 | 217.52 | 5636.00 |
| B | Beam and Column | sqmtr | 263.93 | 544.45 | 143697.00 |
| C | Slab & Chhaja | sqmtr | 135.08 | 363.29 | 49073.00 |
| D | Stair Case | sqmtr | 13.87 | 437.43 | 6067.00 |
| E | Plainth Band | sqmtr | 43.18 | 87.03 | 3758.00 |
| 11 | Supplying & Fixing of FRP door with frame of size 75mmX100mm including drilling holes in masonary walls,all cost of labour, material & conveyance etc. Complete as per direction of Engineer-in-charge. | Rmtr | 37.34 | 481.50 | 17979.00 |
| 12 | Supplying & Fixing of Factory made single leaf rigid F.R.P composite door shutter of 32 mm thick, laminated with GPP skins with wood grain finished including all cost of labour, material & conveyance etc. complete as per direction of Engineer-in-charge. | Rmtr | 12.80 | 5041.10 | 64526.00 |
| 13 | Supplying ,fitting, fixing of wildow (sliding type) made of aluminium section 9778 as windiws frame section No. 4095,4096 and S shutter frame with 5mm thick pinhead glass as panel fitted with rubber bending including licking arrangement including all fitting including cost of materials all taxes, labour , T & P etc. Complete as per direction of Engineer-in-charge. | sqmtr | 24.95 | 2393.49 | 59718.00 |
| 14 | Providing and supplying, fitting fixing M.S. grills and iron shutters in widows & doors including cost of screws and all materials labours required for the work,fabrication charge, transportation etc. complete and as per direction the Engineer-in-Charge. | Kg | 771.50 | 65.40 | 50456.00 |
| 15 | 6 mm thk. Cement plaster in CM 1:4 to RCC surface including deep chipping & slurry treatment ith watering curring,finishing,smooth surface including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc.complete in all floors as per direction of the Engineer-in-charge. complete. | sqmtr | 117.74 | 120.50 | 14188.00 |

| | | | | | |
|----|--|-------|--------|---------|----------|
| 16 | Supplying, Fitting , Fixingof vetrified tiles 600mmX600 mm plain ivory in dados of approved quality including preparing the bed and spreading 12 mm thick bed in cement mortar(1:3) using sand and cement of approved grade and quality from approved quarry with all leads and lifts conforming to relevant codes, mixing in right proportion and laying and curing for required period as per the specification including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | SqMt | 3.20 | 1149.10 | 3677.00 |
| 17 | Supplying, Fitting , Fixingof vetrified tiles 600mmX600 mm plain ivory in Floors of approved quality including preparing the bed and spreading 20mm thick bed in cement mortar(1:3) using sand and cement of approved grade and quality from approved quarry with all leads and lifts conforming to relevant codes, mixing in right proportion and laying and curing for required period as per the specification including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | sqmtr | 110.44 | 822.80 | 90870.00 |
| 18 | Supplying & Fixing Ceramic glazed Tile in toilet wall cladding over cement mortar 12 mm thick 1:3 including pointing the joints with matched pigment mixed with white cement 1:1 etc complete in all respects.complete as per the specification and direction of the Engineer-in-charge. | sqmtr | 55.60 | 611.50 | 33999.00 |
| 19 | Supplying & Fixing 30mm thick PVC Door with both side commercial including all fittings & fixtures all material, labour, conveyance etc. Complete as per direction of Engineer-in-charge. | sqmtr | 6.30 | 2278.00 | 14351.00 |
| 20 | Painting two coats enamel paint over once coat of primer to door and window with any approved enamel paint including cost of all materials etc complete. as per direction of the Engineer-in-charge. | sqmtr | 56.86 | 129.05 | 7338.00 |
| 21 | Finishing wall surface with two coat of water proofing weather coat of approved quality including preparing the background and applying in required quantity uniformly over the wall and finishing smooth including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | sqmtr | 255.57 | 52.10 | 13315.00 |
| 22 | Finishing wall surface with cement based wall putty of approved make including preparing the background by rubbing with wire brush, brooming and applying Acrylic putty mixing in right proportion with water and finishing smooth to required thickness including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | sqmtr | 685.52 | 58.10 | 39829.00 |
| 23 | Painting two coats of plastic emulsion paint to inner side over ceiling area with any approved enamel paint including cost of all materials etc complete. as per direction of the Engineer-in-charge. | sqmtr | 685.52 | 59.30 | 40651.00 |
| 24 | 25mm thick grading concrete in CC (1:2:2) over roof slab with 4.7 mm size H.G Chips after raking out the joints with watering curring,finishing,smooth surface including cost and conveyance of all materials and labour with T&P required for the work with all taxes and royalties etc.complete in all floors as per direction of the Engineer-in-charge. | sqmtr | 15.79 | 217.20 | 3430.00 |
| 25 | Supplying, fitting, fixing of Stainless steel of 304 grade in hand railing using 50 mm dia of 2mm thick circular pipe with balustrade of size 32mmX32mmX2mm in 3 rows in stair case as per approved design and specification, buffing, polishing etc. with cost, conveyance, taxes of all materials, labour T&P etc complete as per the direction of Engineer-in-Charge. | Rmt | 7.62 | 3393.80 | 25861.00 |

| | | | | | | |
|--|---|-------|-------|--------|------------------------------|-------------------|
| 26 | Providing fitting and fixing of False ceiling with Aluminium anodised T Section No. 3215 with 2'0" center to center, L Section No. 1705 upto 15 micron on 4 walls to be fixed by means of steel screw and PVC plug and the Aluminium grid 2'0" x 2'0" with pre laminated particle board suspended from ceiling etc complete including cost, conveyance, royalty, taxes, labour charges, T&P as per the specification and direction of the Engineer-in-charge but excluding GST. | sqmtr | 59.13 | 987.22 | 58374.00 | |
| | | | | | TOTAL RS | 1921418.00 |
| | | | | | Total Estimated cost- | 1921418.00 |
| My Quoted rate is at Current Shedule of Rate/ % Less/Excess than estimated cost | | | | | | |

Approved for 26(Twenty Six) items only amounting to Rs 19,21,418.00 Rupees(Ninteen Lakh Twenty One Thousand Four hundred Eighteen) only.

Sold vide M R No _____ Date _____

Signature of Issuing Authority

Addl P D (Tech)
D.R.D.A.,Kalahandi

BID IDENTIFICATION NO. JAIPATNA BLOCK, KLD- 01 /2018-19



GOVERNMENT OF ODISHA

PANCHAYATI RAJ & DRINKING WATER DEPARTMENT

(Civil Works)

DETAILED TENDER CALL NOTICE FOR THE WORK:

| Sl No. | Name of the Project | Estimated Cost |
|--------|---|------------------|
| 1 | Construction of Box Cell Culvert on the road from School pada (Nagupada) to Sadargudi (Nagupada) | RS. 41,89,026.00 |
| 1 | Construction of New ICDS Building at Jaipatna, GP. JAIPATNA | RS. 19,21,418.00 |

Contractor

BDO

Page | 1

OFFICE OF THE PANCHAYAT SAMITI JAIPATNA, KALAHANDI

BID IDENTIFICATION No: JAIPATNA BLOCK, KLD / 01 / 2018-19

No . 01/ Jpt/ Dtd.

The **BDO JAIPATNA** on behalf of Governor of Odisha invites **Percentage Rate** bids in single cover system for the construction of works as detailed in the table, from the class of eligible contractors as mentioned in column-5 (five) registered with the State Governments and Contractors of equivalent Grades / Class Registered with Central Government / MES / Railways, to be eventually drawn up in PWD **P-1 Agreement** form, for execution of Buildings i.e. **civil works**. The proof of registration from the appropriate authority shall be enclosed along with the Bid. If successful, the bidder who has not registered under state government has to register under the state PWD in appropriate class of eligibility before signing of the agreement. The bidders may submit bids for the following work.

TABLE -1

| Sl no | Name of the Work | Approximate Value of work (In Rs.) | Period of completion | Class of contractor | EMD.Bid security @ 1% | Cost of Bid document |
|-------|---|------------------------------------|----------------------|---------------------|-----------------------|----------------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Construction of Boxcel culvert on the Road from School pada (Nagupada) to Sadargudi(Nagupada) GP- PKMUNDI, Jaipatna Block | 41,89,026.00 | Four Calendar Month | B & A | 42,000.00 | 6000.00 |
| 2 | Construction of New ICDS Building at Jaipatna, GP. JAIPATNA | 19,21,418.00 | Four Calendar Month | D & C | 20,000.00 | 6000.00 |

1. Bid documents consisting of plans, specification, the schedule of quantities and the set of terms & conditions of contract and other necessary documents can be seen in the office of the undersigned during office hours every day except on Sunday & Public holidays till last date of sale and receipt of tender paper. The Bid documents will also be available in the district website <http://kalahandi.nic.in> from Date **26.11.2018 11 AM to 06.12.2018 5PM**.

Contractor

BDO

Page | 2

2. Bids must be accompanied with E.M.D. (Bid Security) of the amount specified for the work in the table **Col.6** above in shape of N.S.C./P.O.T.D / Post Office Savings Pass Book / Deposit receipt of any Scheduled Bank (Valid minimum one year from the date of receipt) duly pledged in favour of **BDO JAIPATNA**. Bidders desirous to hire machineries or equipments from outside of the State are required to furnish 2% of the amount put to tender as bid security instead of 1%. Bids without E.M.D. or in other shape will not be considered and liable for rejection.
N.B:- E.M.D. in shape of Cash / Pay Orders or Bankers Cheques / Bank Draft is not acceptable.
3. The sale of the Bid document shall start from **Dt. 26.11.2018 at 11 AM** and **close on Dt. 06.12.2018 at 5.00 P.M.** during office hours in the office of the under signed. The Tenderers delivered the tender documents along with the relevant documents of one work in the sealed cover with caption the name of the work over the envelop. Bids shall be received through Registered Post/ Speed Post with AD, on or before **Dt.10.12.2018 at 5.00 P.M.** The authority will not be held responsible for any Postal delay in delivery of the Bid documents or non-receipt of the same.
4. The Bid will be opened on **Dt.12.12.2018 at 11.00 A.M.** in the office of the undersigned in the presence of the members of the Block Level Tender/Purchase Committee and the bidders or their authorised representative. If the office happens to be closed on the date of receipt / opening of the bids as specified, above will be received / opened on the next working day at the same time and venue.
5. Bid documents can be purchased from this Agency on payment of the tender cost mentioned against the work in **Col. 7** in shape of cash or DD drawn in favour of **BDO JAIPATNA** payable at KALAHANDI from any Nationalized scheduled Bank towards cost of tender paper. This is non-refundable.
6. The tender documents can be downloaded from district website <http://kalahandi.nic.in> on payment of tender cost of Rs 6,000.- (Rupees Six Thousand Only) each set in shape of Demand Draft in favour of **BDO JAIPATNA** and submit the Demand Draft in a separate envelope marked "COST OF TENDER DOCUMENT DOWNLOADED FROM INTERNET" alongwith the tender.
7. Balance Bid security @ 1% of contract value shall be pledged in parts in favour of **BDO JAIPATNA** corresponding to the respective value of works and deposited during drawl of agreement.
8. Bidders shall submit original affidavit regarding authenticity of their documents and E.M.D along with their bids. Bids shall be accompanied with attested true copy of valid registration certificate, valid GST clearance certificate and PAN card, otherwise his/her bids shall be declared as non-responsive and thus liable for rejection. The original certificates of the lowest three bidders are to be produced before Executive Engineer, DRDA, KALAHANDI for verification.
9. Other details can be seen in the bidding documents.
10. Checklist is to be duly filled in.
11. Engineer Contractors desirous to avail the facility of exemption of E.M.D. is required to submit an affidavit to the effect that he has not yet availed the facility for more than two works during the current financial year. The name of work for which and the authority to which the tender is being submitted must be mentioned in the affidavit failing, which the tender will be rejected.

12. The ST/SC contractor desires to avail price preference are required to submit an affidavit.
13. The name of work for which and the authority to which the tender is being submitted must be mentioned in the affidavit failing, which the tender will be rejected.
14. Additional Performance Security shall be obtained from the bidder when the bid amount is less then estimated cost put to tender. In such an event, only the successful bidder who has quoted less bid price/rates than the estimated cost put to tender shall have to furnish the exact amount of differential cost i.e. estimated cost put to tender minus the quoted amount as additional performance Security (APS) in shape of Term Deposit Receipt pledged in favour of Divisional Officer/Bank Guarantee in favour of the Divisional Officer from any Nationalized/Scheduled Bank in India. Counter guaranteed by its local branch at Block within seven days of issue of Acceptance (LoA) BY THE Divisional Officer (by e-mail) to the successful bidder otherwise the bid of the successful bidder shall be cancelled and the Earnest Money Deposit/Bid Security shall be forfeited. Further proceeding for blacklisting shall be initiated against the bidder.
15. Any corrigendum / Addendum will be displayed in the website <http://kalahandi.nic.in> only.
16. Conditional tender will summarily be rejected.
17. Building and other Construction Workers Welfare Cess @ 1% (One Percentage) of the cost of construction shall be deducted from bills.
18. Rate shall be putted in percentage both in figure and word writing excess or less into one decimal point shall be considered infect round off.
19. **The items covered in Clause No- 147 of DTCN are required as essential criteria for eligibility for qualification.**
20. The authority reserves right to reject any or all the bids without assigning any reason thereof.

Sd
Block Development Officer
JAIPATNA Block

Memo No _____ Dt. 24.11.2018

Copy to The Editor , The Sambad Bhubaneswar, The Prameya Bhubaneswar, The Samaj and The India Post, Bhubaneswar for advertisement in there News-paper. He should submit a copy of advertisement along with bill limited to Rs 5,000/- for payment of advertisement charges. It is

requested to get the tender notice published consuming size 10 cm x 10 cm space, before Dt...06.12.2018 in one issue only for wide publication. The complementary copies for the same may please be sent to this office for reference and record.

Sd/-
Block Development Officer
JAIPATNA Block

Memo No. _____ Dt. 24.11.2018

Copy along with soft copy of the notice submitted to the D.I.O., NIC, Kalahandi with a request to display the Tender call Notice and Tender document in the Web-site till 5 PM ofdt 06.12. 2018 Enclose:-Soft copy 1 no.

Sd/-
Block Development Officer
JAIPATNA Block

Memo No. _____ / Dt. 24.11.2018

Copy submitted to the Collector cum District Magistrate, Kalahandi / Superintendent of Police/ OIC
JAIPATNA Police Station , Kalahandi for kind information and necessary action.

Sd/-

**Block Development Officer
JAIPATNA Block**

Memo No. _____ Dt. 24.11. 2018

Copy to Notice Board of Block office for wide circulation.

Sd/-

**Block Development Officer
JAIPATNA Block**

Tender Inviting Authority:- Block development Officer, JAIPATNA

| Name of the Work:- | | Construction of Boxcel Culvert on the Road from School pada (Nagupada) to Sadargudi (Nagupada) | | | |
|---|---|---|-----------------|-----------------------|---------------|
| Class of Contractor: 'B' & 'A' | | E M D 1% of estimated Cost | | | |
| Bid Identification no;-01 | | Estimated cost put to tender:-41,89,026.00 | | | |
| Bill of Quantities | | | | | |
| SI No | Description of works | Unit | Quantity | Estimated Rate | Amount |
| | 6.00m x 3.00 m x 3 span | | | | |
| 1 | Dismantling brick or stone masonry in lime or cement mortar above 3 m height including stacking the useful materials for reuse and removing the derbis within 50 m lead. etc complete as per the direction of Engineer-in-Charge. | cum | 70.55 | 828.52 | 58452.00 |
| 2 | Earth work in excavation of foundation trench in all kinds of soil with all leads and lifts including levelling the bed and finishing the sides of the foundation trench truly vertical and ramming the bed after back filling the weak spots sprinkling water, removing roots and shrubs breaking the clounds to maximum 5 to 7 cm size and depositing the excavated materials away from the working area including including cost of labour, T&P etc complete as per the specification and direction of the Engineer-in-charge. | cum | 498.89 | 134.43 | 67066.00 |
| 3 | Filing foundation and plinth with sand of approved quality from approved quarry with all leads and lifts, well watered and rammed to required depth including cost, conveyance, royalty, all taxes of materials, labour charges, T&P etc. complete as per specification and direction of Engineer-in-charge but excluding GST. | cum | 165.88 | 369.54 | 61299.00 |
| 4 | Cement Concrete(1:3:6) using 40 mm size crusher broken hard HG metal, sand and cement of approved grade and quality from approved quarry in foundation including all cost, carriage, royalty taxes etc. complete including mixing, hoisting, lowering, laying and compacting to required thickness in layers of 15 cm depth, curing for required period including cost of labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | cum | 72.28 | 3618.53 | 261547.00 |
| 5 | Providing and laying Plain cement concrete M-15 for open foundation mechanically mixed and compacted complete as per drawings and Technical specifications and as directed by the Engineer-in-charge. | cum | 116.79 | 3596.12 | 419991.00 |
| 6 | Reinforced Cement Concrete in(1:2:4) using 20 mm size and down graded hard granite chips, sand and cement of approved grade and quality conforming to relevant codes from approved quarry with all leads and lifts including mixing in right proportion, hoisting, lowering, laying in layers not exceeding 15 cm in thick and compacting by means of vibrator to required density, line, grade and camber including providing centering and shuttering and curing for required period including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | cum | 58.48 | 4544.28 | 265749.00 |
| 7 | Reinforced Cement Concrete in(1:1:2) using 12 mm size crusher broken hard granite chips, sand and cement of approved grade and quality conforming to relevant codes from approved quarry with all leads and lifts including mixing in right proportion, hoisting, lowering, laying in layers not exceeding 15 cm in thick and compacting by means of vibrator to required density, line, grade and camber including providing centering and shuttering and curing for required period including cost, conveyance, royalties, all taxes, labour, T&P etc complete as per the specification and direction of the Engineer-in-charge but excluding GST. | | | | |
| a | Below Bed Level | cum | 76.50 | 4619.21 | 353370.00 |
| b | Above Bed Level | cum | 58.05 | 4715.00 | 273706.00 |
| c | Deck slab of box | cum | 76.50 | 6242.47 | 477549.00 |

| | | | | | |
|----|---|-------|---------------|----------------|-------------------|
| 8 | Construction of RCC railing of M30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, centre to centre spacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical space between vertical post for expansion, complete as per approved drawings and technical specifications and direction of Engineer-in-charge. | Rmt | 93.75 | 1469.27 | 137744.00 |
| 9 | Construction of RCC railing of M30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, centre to centre spacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical space between vertical post for expansion, etc. complete as per approved drawings and technical specification. | cum | 11.48 | 4609.60 | 52918.00 |
| 10 | Straightening bend up or coiled rod cutting, bending, cranking, hooking, welding or jointing (if required) the M.S. Rods or Tor steel and binding wires and binding, tying the grills, hoisting, lowering and placing in proper position as required for R.C.C. works including cost, conveyance and taxes of M.S. Rods or Tor steel and binding wires of 18 to 20 gauge and labour with all T&P required for the work etc.complete in all floors (weight of binding wires will not be considered for payment and payment will be made on weight of M.S. rods or Tor steel only) as per direction of the Engineer-in-charge. | | | | |
| a | F&P | qtl | 65.03 | | |
| b | Sub Structure | qtl | 49.41 | | |
| c | Super Structure | qtl | 70.39 | | |
| | TOTAL | qtl | 184.83 | 6243.10 | 1153912.00 |
| 11 | Rough stone dry packing in aprons and revetments, stone pitching in slopes and boulder apron of CD works, bridge work etc with hard stone of size 30 cm and above and weighing not less than 40Kg as per approved drawing and Section 2500 (Clause 2504) of specifications for road and bridge works of Ministry of Road Transport & Highways (5th Revision) & including cost of all materials, labour, T&P, taxes, royalty etc complete in all respect and as per direction of the Engineer-in-charge. | cum | 63.20 | 1061.21 | 67068.00 |
| 12 | Providing Gravel backing to aprons & revetments and providing filter material using gravel underneath pitching in slopes as per approved drawing and technical specifications as per Section 900, 1000 & 2500 (Clause 2504.2.2) of MoRT&H Specifications for Road & Bridge works (5th Revision) and as per direction of Engineer-in-Charge. | cum | 33.60 | 562.40 | 18897.00 |
| 13 | Providing & laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm with 40mm metal providing over the entire surface behind abutment, wing wall, return wall etc. complete as per specification and direction of Engineer-in-Charge. | cum | 54.79 | 1568.29 | 85927.00 |
| 14 | Cement washing two coats with 1st mark cement paint of approved quality to exterior surface of bridge proper including watering, curing, cost and conveyance of all materials etc. complete as per the direction of the Engineer-in-Charge. | sqmtr | 113.40 | 17.30 | 1962.00 |
| 15 | Providing weep holes in abutment and retaining wall of CD works, bridge work etc with 100mm dia A.C. pipe as per approved drawing and technical specifications as per Section 2200, 2700 (Clause 2706) of MoRT&H Specifications for Road & Bridge works (5th Revision) and as per direction of Engineer-in-Charge. | Rmtr | 40.00 | 100.66 | 4026.00 |
| | BT ROAD | | | | |
| 16 | Earth work in excavation in ordinary soil for bridge works etc as per drawing and technical specification, including setting out, dressing of section to correct line, level, grade & camber and loading into tippers, transporting to embankment site within all lifts and lead upto 1000mtr. and utilising the surplus earth locally for road work wherever required, backfilling the excavation earth to the extent required complete in all respect as per Clause 301 & 304 of Specification for road & bridge work of MORT&H (5th Revision) & Direction of Engineer in charge. | cum | 1005.47 | 172.03 | 172971.00 |

| | | | | | |
|----|--|-------|--------|-----------------------|------------|
| 17 | Construction of Granular Sub-base Grade-III by providing well graded material, spreading in uniform layers with motor grader on prepared surface mixing by sand moorum admixture etc. complete as per the direction of Engineer-in-Charge. | cum | 42.53 | 464.17 | 19741.00 |
| 18 | Fine dressing and turfing to the slopes of the road embankment(initial lead of 50 m and 1.5 m initial lift) with compact dub gross transported by mechanical means as per the direction of the E.I.C. | sqmtr | 168.00 | 15.02 | 2523.00 |
| | TOE WALL | | | | |
| 19 | Earth work in excavation of foundation & plinth in hard soil including dressing of sides and levelling the bed up to the required depth and depositing the excavated materials away from the work site within 50m initial lead & 1.5m initial lifts with sundries & T&P required for the work complete including cost of all labour,labour cess,T&P,sundries etc. as directed by the Engineer in charge. | cum | 47.52 | 134.43 | 6388.00 |
| 20 | Filing foundation and plinth with sand of approved quality from approved quarry with all leads and lifts, well watered and rammed to required depth including cost, conveyance, royalty, all taxes of materials, labour charges, T&P etc. complete as per specification and direction of Engineer-in-charge but excluding GST. | cum | 7.92 | 369.54 | 2927.00 |
| 21 | Providing and laying plain cement concrete of proportion (1:3:6) in foundation using 40 mm size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar of approved quality and from approved quarry including hoisting, lowering, laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15 cm. thick in each layer including cost, conveyance, royalties, taxes of all materials and cost of all labours,labour cess, T&P etc complete as per the direction of the Engineer-in-charge. | cum | 7.92 | 3618.53 | 28659.00 |
| 22 | Providing and laying plain cement concrete of proportion (1:3:6) in Sub-structure using 40 mm size black hard crusher broken granite stone metal and screened and washed sharp sand for mortar of approved quality and from approved quarry including hoisting, lowering, laying concrete, ramming, watering and curing etc. complete to required levels laid in layers not exceeding 15 cm. thick in each layer including cost, conveyance, royalties, taxes of all materials and cost of all labours,labour cess, T&P etc complete as per the direction of the Engineer-in-charge. | cum | 49.50 | 3618.53 | 179117.00 |
| 23 | Rough stone dry packing in aprons and revetments, stone pitching in slopes and boulder apron of CD works, bridge work etc with hard stone of size 30 cm and above and weighing not less than 40Kg as per approved drawing and Section 2500 (Clause 2504) of specifications for road and bridge works of Ministry of Road Transport & Highways (5th Revision) & including cost of all materials, labour, T&P, taxes, royalty etc complete in all respect and as per direction of the Engineer-in-charge. | cum | 13.20 | 1061.21 | 14008.00 |
| 24 | Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and direction of EIC. | mtr | 15.00 | 100.60 | 1509.00 |
| | | | | TOTAL RS | 4189026.00 |
| | | | | Total Estimated cost- | 4189026.00 |
| | My Quoted rate is at Current Shedule of Rate/ % Less/Excess than estimated cost | | | | |

Approved for 24(Twenty Four) items only amounting to Rs 41,89,026.00 (Rupees Forty One Lakh Eighty Nine Thousand Twenty six) only.

Sold vide M R No _____ Date _____

Signature of Issuing Authority

Addl P D (Tech)
D.R.D.A.,Kalahandi